Office of the Community
Services Director

ADDENDUM NO. 2

FACILITY ROOF REPAIRS

CITY PROJECT NO. 15-BLDG-05

October 19, 2015

The following are responses to questions raised during the bidding process, contract clarifications and scope of work clarifications:

The Detailed scope of work includes, but not limited to the following:

1. Clean and prepare the roof surface including power washing the entire roof
2. Clean all roof drains/scuppers
3. Cut and properly fasten loose cap sheets including walls
4. Install new Detail Cap Sheet at cut locations
5. Apply new two (2) part epoxy primer
6. Install Three (3) Course Silicone along all wall edges and drains
7. Install new silicone coating at rate of 2 - 3 gallons per SQ's Entire Roof
8. Clean all roofing debris and haul away
9. All other contract and specification requirements remain unchanged.

Due to the late issuance of Addendum No. 2, the Bid Opening date has been extended to 10:30 AM on Tuesday, October 27, 2015.

Please sign below and attach this "ACKNOWLEDGMENT OF RECEIPT", Addendum No. 2 with your bid submittal documents. Thank you for your cooperation.

Sincerely,

Doug Benash, P.E.
City Engineer

ACKNOWLEDGMENT OF RECEIPT: Addendum No. 2

_____ _____
Company Name Date

By_____
Signature

www.cityoflapalma.org
7822 Walker Street
La Palma, CA 90623-1771
PHONE 714 690 3300
FAX 714 523 2141